

Capital Project Cost Estimate Template

Company: DEQP
Project Owner: tbd
Capital Project Name: GOSHEN,
Project Priority:

by G.Vance, last revised
3/3/2020

Justification:

* tap ML104 at DEQP's site (GOSHEN)

Scope of work

- 4" tap on ML104 at GOSHEN site
- 4" slam shut valve, 3" ultrasonic meter sized for 9.1 MMSCFD nominal at 650 psig nominal, 12.3 MMSCFD max
- Grassroots Encal building, gas chromatograph in climate controlled building
- MAOP of all equipment to match MAOP of ML104 (1370 psig MAOP), no pressure control
- delivery pressure to match existing (typically runs about 650 psig), no pressure control or flow control will be provided by DEQP

Excluded, (or by others)

- pressure control, flow control: by others
- odorization: by others
- Pipeline leaving the Site: by others
- filtration: by others
- data sharing of meter flowrate: Not required. DEU will provide separate meter to determine odorization rate.