

ELECTRIC SERVICE SCHEDULE NO. 113 - Continued
QUALIFYING EQUIPMENT: (continued)

Customers installing a new whole-house distribution system with a non-premium evaporative cooler will qualify under the New Evaporative equipment incentive tier.

All central air conditioning equipment must be a new air-source split or packaged unitary air-conditioner with an Air-Conditioning and Refrigeration Institute (ARI) Standard Rating Cooling Capacity of 65,000 Btu/hr (5.4 tons) or less, and must contain either a factory or field installed thermal expansion valve.

Split-system central air conditioning equipment must include a matched condensing unit and evaporative coil with an overall efficiency rating as determined by ARI Standard 210/240.

To qualify for the sizing incentives identified in Table 1A, central air conditioner equipment must match the calculated cooling load of the residence where it is installed. The cooling load calculation must be based on methodology in Air Conditioning Contractors of America (ACCA) Manual J and the mandatory cooling load calculation assumptions provided in the Cool Cash Incentive program manual for participating dealers. Installed equipment is considered properly sized when its Standard Capacity Rating as reported in the current AHRI Directory of Unitary Equipment is within one-half ton (6,000 Btu/hr) of the calculated cooling load.

To qualify for proper installation incentives identified in Table 1A, the central air conditioner must be installed according to the requirements provided in the Cool Cash Incentive program manual for participating dealers. In addition, installation documentation must be completed and signed by a certified North American Technician Excellence (NATE) dealer.

INCENTIVES: Customer incentives are listed in Table 1A and are effective for qualifying equipment fully installed at the customer site after January 1, 2009.

Table 1A. Program Incentive Levels

Qualifying Measure	Customer Incentive	Dealer Incentive
Replacement Evaporative	\$100	\$25
New Evaporative	\$300	\$25
Premium Evaporative	\$500	\$150
Premium Whole-House Evaporative	\$1,000	\$300
Properly Sized CAC Equipment + TXV	\$50	\$25
Properly Installed CAC Equipment + TXV	\$50	\$75
15.00+ SEER/12.5+ EER CAC Equipment + TXV	\$150	\$0

(continued)

 (L)
 frm
 p.1

(C)

(C)

(C)

(I)

(I)

(N)

(I)