

BEFORE THE PUBLIC SERVICE COMMISSION OF UTAH

In the Matter of the Application of)	Docket No. 10-035-13
Rocky Mountain Power for Authority for)	
Alternative Cost Recovery for Major)	Direct Testimony of
Plant Additions of the Ben Lomond to)	Randall J. Falkenberg
Terminal Transmission Line and the Dave)	On Behalf of the
Johnston Generation Unit 3 Emissions)	Utah Office of
Control Measure)	Consumer Services

April 26, 2010

1 **Direct Testimony of Randall J. Falkenberg**

2 **Q. PLEASE STATE YOUR NAME AND BUSINESS ADDRESS.**

3 **A.** Randall J. Falkenberg, PMB 362, 8351 Roswell Road, Atlanta, Georgia 30350.

4 **Q. PLEASE STATE YOUR OCCUPATION, EMPLOYMENT, AND ON**
5 **WHOSE BEHALF YOU ARE TESTIFYING.**

6 **A.** I am a utility regulatory consultant and President of RFI Consulting, Inc. (“RFI”).

7 I am appearing on behalf of the Office of Consumer Services (“the OCS”).

8 **Q. WHAT CONSULTING SERVICES ARE PROVIDED BY RFI?**

9 **A.** RFI provides consulting services related to electric utility system planning, energy

10 cost recovery issues, revenue requirements, cost of service, and rate design.

11 **Q. PLEASE SUMMARIZE YOUR QUALIFICATIONS.**

12 **A.** My qualifications and appearances are provided in Exhibit OCS 3.1.

13 **Introduction and Summary**

14 **Q. WHAT IS THE PURPOSE OF YOUR TESTIMONY?**

15 **A.** My testimony addresses PacifiCorp’s (“the Company”) Generation and

16 Regulation Initiatives Decision (“GRID”) model study of the Net Power Costs

17 (“NPC”) impact of the Dave Johnston 3 scrubber and the Ben Lomond to

18 Terminal transmission line.

19 **Q. PLEASE OUTLINE PACIFICORP’S NPC REQUEST IN THIS CASE.**

20 **A.** PacifiCorp requests to increase Total Company NPC by \$1.635 million resulting

21 in a Utah NPC increase of \$671 thousand. These amounts would then be

22 reflected in the alternative cost recovery for these two projects.

23 **Q. PLEASE SUMMARIZE YOUR TESTIMONY.**

24 **A.** I have identified a number of issues related to the Company’s filing. Table 1

25 shows the impact of each issue and they are summarized below:

Table 1

Requested NPC	Total Company	Utah
Docket 09-035-23 Commission Approved NPC	1,002,942,591	410,927,346
Company Requested NPC Increase	1,635,206	671,008
Resulting Company Requested NPC	1,004,577,796	411,598,354
OCS Adjustments		
1 Compliance GRID Study Offset	(647,779)	(265,817)
2 Correct Heat Rate Error	(659,913)	(270,796)
3 Remove Heat Rate Adjustment	(291,962)	(119,807)
Total OCS Adjustments	(1,599,655)	(656,420)
Resulting NPC Increase Recommended	35,551	14,588
Total Allowed NPC	1,002,978,142	410,941,935

26

27 1. The Company proposes to increase the Commission approved Total
 28 Company NPC in Docket No. 09-035-23 (\$1,002.9 million) by \$1.635
 29 million. OCS recommends an increase of only \$35,551 Total
 30 Company or \$14,588 Utah.

31

32 2. The Company proposes to quantify the NPC impact of the Dave
 33 Johnston 3 scrubber based on its final rebuttal GRID study from
 34 Docket No. 09-035-23. I recommend that instead the NPC impact be
 35 measured against a compliance GRID study that implements all of the
 36 Commission's approved adjustments in that case. This provides a
 37 more consistent and less subjective basis for determining NPC
 38 impacts.

39

40 3. A GRID study which implements all of the NPC adjustments
 41 approved in Docket No. 09-035-23 results in a Total Company NPC
 42 \$648 thousand less than the NPC approved in the final order in that
 43 case. This is due to interaction among the Commission approved
 44 adjustments. OCS recommends the Commission offset the requested
 45 increase to account for these differences.

46

47 4. The Company acknowledges various errors in its calculation of the
 48 heat rate inputs for the Dave Johnston 3 scrubber. Correcting the
 49 heat rate inputs results in a decrease to NPC of \$660 thousand (\$271
 50 thousand Utah).

51

52 5. The Company's usual method for modeling heat rates compares four
 53 year actual to predicted design heat rate results. This process would
 54 reflect heat rate degradation due to the scrubber over time. The
 55 Company has not historically made heat rate adjustments for

56 efficiency improvement projects. Consequently, I recommend the
57 Commission reject the remaining heat rate degradation adjustment,
58 reducing NPC by \$291 thousand Total Company or \$120 thousand
59 Utah.
60

61 **NPC Impact Analysis**
62

63 **Q. HOW DID THE COMPANY QUANTIFY THE NPC RESULT IN THIS**
64 **CASE?**

65 **A.** Dr. Shu testified on page 3 as follows:

66 “The Company believes that the intent and purpose of the alternative cost
67 recovery mechanism for major plant additions is to calculate the incremental
68 difference caused by adding the new plant addition *between base rates from the*
69 *most current general rate case*. It was not the intent of this recovery mechanism
70 to update assumptions or forecasts.” (Emphasis added)
71

72 The Company used its rebuttal GRID study from Docket 09-035-23 as the
73 basis for determining the incremental cost impacts of the Dave Johnston 3
74 scrubber. Dr. Shu declined to correct a minor error in the Dave Johnston 3
75 capacity on the basis of the reasoning quoted above.

76 **Q. DO YOU HAVE A SIMILAR UNDERSTANDING OF THIS CASE?**

77 **A.** In general, yes. Correcting the Company’s errors in the GRID model, or making
78 new updates could complicate this process substantially, possibly creating a “do-
79 over” scenario where parties argue about points already decided or try to uncover
80 new errors or omissions in the Company filing.

81 **Q. HOW DID YOU MAKE THE NPC DETERMINATION IN THIS CASE?**

82 **A.** I determine the NPC impact of the plant additions as they would have been
83 determined were they a pro-forma adjustment to the prior rate case. This should
84 be consistent with the Commission’s final order. Rather than using the
85 Company’s rebuttal GRID run for determining the NPC impact of major plant
86 additions it would be preferable to implement all adjustments approved in the
87 final order into the GRID model, and use that study as the basis for determining

88 any NPC adjustment. Because the Company's filing was made prior to the
89 decision in Docket No. 09-035-23, the Company could not follow such a
90 procedure. As I will explain shortly, there is always the possibility of an
91 interaction among adjustments. This means there could be differences in the final
92 NPC results if the rebuttal position is used as opposed to a study that implements
93 Commission approved adjustments. To be consistent with the Commission
94 decision in the general rate case, I implement all Commission approved
95 adjustments in the GRID model and use it as the benchmark for this case.

96 **Q. IS THIS APPROACH CONSISTENT WITH THE COMPANY'S**
97 **POSITION AS STATED IN THE SUPPLEMENTAL TESTIMONY OF**
98 **MR. MCDUGAL?**

99 **A.** Yes. Mr. McDougal testifies on page 1 of his supplemental testimony that the
100 revisions he sponsored were to "...comport with the final revenue requirement
101 approved by the Commission in Docket No. 09-035-23..." However, the
102 Company made no such changes to the GRID study, and continues to request the
103 amount computed based on the rebuttal GRID model run.

104 **Q. WHAT ADJUSTMENTS DID YOU MAKE TO THE GRID MODEL?**

105 **A.** Listed below are the Commission approved adjustments (and supporting party)
106 from Docket No. 09-035-23 that I included in the compliance GRID model study:

- 107 1. SMUD Contract Price (RMP)
- 108 2. MagCorp Reserves/Kennecott Incentive Contracts (DPU)
- 109 3. Wyodak Heat Rate (DPU)
- 110 4. Lewis River Corrections (OCS)
- 111 5. OCS Wind Split (OCS)
- 112 6. High Plains and McFadden Start Dates (DPU)
- 113 7. MagCorp QF, Kennecott QF, Tesoro QF (DPU)
- 114 8. BPA Wind Integration (RMP)
- 115 9. BPA Peaking and Grant PUD (RMP)
- 116 10. Gas Plant Outage Rates (OCS)
- 117 11. Outage Schedule (DPU)
- 118 12. SMUD Contract Normalization (OCS)

- 119 13. Biomass Contract (OCS)
120 14. Fuel Price Forecast (DPU)
121 15. Daily GRID Screens (OCS)
122

123 **Q. HOW DID YOU PREPARE THE COMPLIANCE GRID STUDY?**

124 **A.** As part of its rebuttal filing in the prior case the Company provided a GRID run
125 which contained the first nine adjustments listed above. As a result, all of those
126 adjustments were based on the Company's work. The input data for the
127 remaining adjustments came directly from the workpapers provided by the
128 Company, OCS or DPU. The only exception to that was the final adjustment
129 which implements the daily screen adjustment approved by the Commission.
130 Like the Company, I implemented adjusted screens for this case.

131 **Q. HOW DID YOU DETERMINE THE SCREENS FOR THE FINAL**
132 **ADJUSTMENT?**

133 **A.** The screens were based on the run which included the first 14 adjustments. I used
134 the same spreadsheets and methodologies as I used in the OCS daily screen
135 adjustment approved by the Commission.

136 **Q. DID THE RESULTING GRID STUDY EXACTLY MATCH THE NPC**
137 **APPROVED IN THE COMMISSION ORDER IN DOCKET 09-035-23?**

138 **A.** No. The result of the compliance GRID study is \$648 thousand *less* than the
139 Commission ordered Net Power Costs. This small difference is not surprising as
140 there is always an interaction between adjustments.

141 **Q. PLEASE EXPLAIN WHAT YOU MEAN BY INTERACTON AMONG**
142 **ADJUSTMENTS.**

143 **A.** In a model like GRID, the final NPC depends on the adjustments to inputs made
144 within the model and the effect of one input may influence the effect of another.
145 The final NPC result may differ from the sum of the values of the individual
146 adjustments. This can happen because adjustments to two different inputs may
147 have complimentary or non-complimentary effects.

148 **Q. PLEASE PROVIDE AN EXAMPLE OF THIS.**

149 A. Assume that the Commission approved adjustments to reduce the outage rate and
150 fuel cost for a coal plant. Reducing the outage rate would increase the generation
151 available for sales and reducing the fuel cost would increase sales margins. If
152 both changes are made, the overall impact is larger than the sum of the two
153 individual adjustments because there is more energy available for sale and it has a
154 bigger margin. These would be complimentary adjustments. If the outage rate
155 were increased, however, then the two adjustments would be non-complimentary
156 as the larger margins would be applied to fewer sales.

157 This happens to some extent with nearly all GRID inputs. As a result, the
158 only way to determine the exact final NPC result is to run the model with each of
159 the individual inputs applicable to the Commission approved adjustments
160 changed.

161 **Q. HAVE YOU IDENTIFIED THE MAJOR REASON WHY THE**
162 **COMPLIANCE GRID RUN PRODUCES A LOWER NPC THAN THE**
163 **COMMISSION ORDER?**

164 A. In this particular case, re-optimizing the daily screens to reflect the approved
165 adjustments produced a larger screening adjustment which is responsible for most
166 of this difference. This occurred because the impact of the screens (designed to
167 correct the unit commitment logic error) depends on the constraints on the system
168 including the market caps. The Commission adopted the daily screens adjustment
169 I proposed, but did not adopt the market cap adjustment. Because the screens I
170 developed for the 2009 rate case assumed the elimination of market caps,
171 implementing screens based only on the approved adjustments yields a different
172 result. In effect, the elimination of the market caps resulted in less uneconomic

173 generation being simulated within the model. With the market caps included in
174 the compliance study, the screens have a larger error to correct. I would note that
175 the Company appears to agree the screens should be recomputed for this case
176 because the Company did so in its GRID study as well.

177 **Q. HOW DID YOU DETERMINE THE NPC IMPACT OF THE MAJOR**
178 **PLANT ADDITIONS IN THIS CASE?**

179 **A.** Based on Dr. Shu's testimony and the discovery OCS performed I accepted the
180 assumption that there is no immediate NPC impact from the transmission line
181 project. As a result, I made the 4.2 MW capacity reduction for the scrubber
182 proposed by the Company and used the corrected heat rate inputs provided by the
183 Company in the Revised Response to OCS 2.8. The result indicates that the NPC
184 increase from the Dave Johnston 3 scrubber would be \$975 thousand on a Total
185 Company basis, or \$400 thousand Utah. This is approximately \$660 thousand
186 less than proposed by the Company in its direct testimony and in Mr. McDougal's
187 supplemental testimony.

188 **Q. HAS THE COMPANY ACKNOWLEDGED ANY CORRECTIONS TO ITS**
189 **NPC IN THIS DOCKET?**

190 **A.** In response to various discovery requests including OCS 2.8, OCS 2.8 Revised
191 and OCS 3.11 the Company confirmed that the heat rate inputs used for Dave
192 Johnston 3 (with the scrubber) in its filing were incorrect and indicated it would
193 file corrected results with its rebuttal. The Company estimates the impact of the
194 scrubber with the corrected inputs is \$1.001 million Total Company. This is quite
195 close to the result from my compliance GRID study (\$975 thousand) if the
196 corrected heat rates are included along with the scrubber capacity reduction.

197 In future cases, there could be a more substantial difference between use
198 of the final Company request (in this case the rebuttal study) and the final
199 Commission approved study, depending on the final adjustments approved by the
200 Commission. Rather than trying to sort out which Commission adjustments
201 should be included, and which can be ignored, or what NPC study should be used
202 as the benchmark, I believe the better approach is to develop a specific procedure
203 applicable to all cases. It makes most sense for that procedure to incorporate all
204 adjustments ordered by the Commission in the last rate case.

205 **Q. DO YOU AGREE WITH THE COMPANY'S PROPOSAL TO REFLECT**
206 **THE REMAINING CORRECTED HEAT RATE IMPACT OF THE**
207 **SCRUBBER?**

208 **A.** No. The Company has taken a rather inconsistent approach to modeling heat rates
209 in this and recent cases. Normally, the Company compares the predicted design
210 heat rate for each generator to the actual input heat rate for a four year historical
211 period. The actual average heat rate will typically exceed the design heat rate and
212 the Company makes an adjustment to reflect heat rate degradation as plants age.
213 Over time this approach will reflect any heat rate changes (whether improvement
214 or degradation) as they occur. With very few exceptions, this is the approach the
215 Company has used for heat rate modeling for many years.

216 While the Company did make an upwards adjustment to the Huntington 2
217 heat rate in recent cases and now proposes to increase the Dave Johnston 3 heat
218 rate in this case,^{1/} it has normally ignored heat rate *improvements* resulting from
219 capital investments. OCS 2.4 and 2.7 show that the Company included close to
220 \$20 million for heat rate improvement projects for Currant Creek, Dave Johnston,

^{1/} In both instances the heat rate adjustment was due to addition of scrubbers.

221 Hunter and Bridger in the test years used in the 2008 and 2009 cases. However,
222 the Company didn't include the associated heat rate improvement in GRID even
223 though they were comparable in magnitude to the heat rate adjustment proposed
224 by the Company in this case. Consequently, there is no basis for assuming it is
225 accepted practice to make pro-forma adjustments for heat rate changes. Because
226 it is inconsistent to reflect assumed heat rate degradation, while ignoring heat rate
227 improvement I recommend the Commission reject the Company's proposed heat
228 rate adjustment.

229 **Q. IS THE ASSUMED HEAT RATE DEGRADATION ALSO SOMEWHAT**
230 **SPECULATIVE?**

231 **A.** Yes. The Company made numerous errors in this case in estimating the impact of
232 the heat rate degradation and has changed its forecast a number of times. In its
233 February filing, Mr. Teply testified that the addition of a scrubber to Dave
234 Johnston 3 would result in a 138 BTU/KWH heat rate increase.^{2/} However, that
235 figure was modeled incorrectly in GRID by the Company and within the next few
236 weeks, the Company proposed three different heat rate assumptions for the
237 scrubber addition – 204 BTU/KWH^{3/}, 268 BTU/KWH^{4/} and finally 219
238 BTU/KWH.^{5/} The Company has never provided the actual basis for the original
239 heat rate assumption. This raises doubt about the Company's ability to accurately
240 predict heat rate changes.

241 Further, it is not clear that the Company has realistically considered all of
242 the impacts of the scrubber on unit performance. The analysis performed by the

^{2/} Direct Testimony of Chad A. Teply, page 5.

^{3/} OCS 2.8

^{4/} OCS 5.1 Confidential Attachment. The Company waived the confidential designation of the quoted figure.

^{5/} OCS 2.8 1st Revised.

243 Company merely considers the additional power requirements of the scrubber (4.2
244 MW). However, Mr. Tepley testifies:

245 Dave Johnston Unit 3 is currently operated with a 220 megawatt net
246 output limit to maintain compliance with state of Wyoming sulfur dioxide
247 (SO₂) emissions limits. The new pollution control equipment will
248 increase the auxiliary power consumption by approximately 4.2 net
249 megawatts. Investment in the new pollution control equipment will
250 remove the net output constraint on the unit associated with sulfur dioxide
251 (SO₂) emissions; however, net output of the unit will likely remain below
252 230 megawatts even after additional minor capital investments are made
253 during the 2014 planned maintenance outage.^{6/}
254

255 Removing the constraint could potentially increase the output of Dave
256 Johnston 3, at least some of the time and as a result improve the heat rate. In the
257 end, the Company's calculations seem speculative and only look at part of the
258 problem. Because the Company's method already allows for a heat rate
259 adjustment process to take place over time, and the Company has not reflected
260 heat rate improvements associated with capital projects, there is little justification
261 for the Company's remaining \$292 thousand heat rate adjustment in this case.

262 **Q. RECOMMENDATIONS?**

263 **A.** I recommend that the Commission measure the NPC impact against a compliance
264 GRID study that implements all of the Commission's approved adjustments in the
265 previous rate case and specify that this is the procedure to be used in all major
266 plant addition cases. I also recommend that the Commission correct the heat rate
267 inputs and remove the heat rate adjustment as described in my testimony.

268 **Q. DOES THIS CONCLUDE YOUR TESTIMONY?**

269 **A.** Yes.

^{6/} Direct Testimony of Chad A. Teply, page 2.